

29979 Harvester Rd, Malibu, CA. 90265 Telephone: (818) 371-7128, e-mail: kodian@verizon.net

DOCUMENT NO. OE-08-10-302

TEST REPORT:

STEELDECK PLATFORM SYSTEMS,

GUARDRAIL

STRUCTURAL CAPACITY

Revision D Dated Nov. 1, 2019

Prepared for:

Steeldeck, Inc. 13147 S Western Avenue Gardena, CA 90249-1921

Approved By:

Kille

Name (print): Title: Kirk Odian President, M.S., P.E.

PROPRIETARY DOCUMENT

The Information herein is privileged and confidential and shall not be disseminated, duplicated, reused or disclosed in any way without the prior written permission of STEELDECK, Inc. or Odian Engineering, Inc.



		Log of H	Revisions
Revision	Page Number	Section	Description of Change
Letter			
IR	all	all	Initial release
А	all	all	Included current CBC 2013 Compliance,
			changed "stage" to "platform".
В	21-30	5.0 & 6.0	Corrected Report Number typo in header.
C	i, v, 1, 6 & 21	Ref., 1.0, 1.2	Included current CBC 2016 Compliance.
D	Cover page	& 5.0	Updated Steeldeck address.



Table of Contents

Log o	f Revisions	i
List o	f Figures	iii
List o	f Tables	iv
Refer	ences	v
1.0	INTRODUCTION	1
1.1	Background	2
1.2	Test Objective	6
1.3	Previous Work	6
1.4	Limitations	8
2.0	EQUIPMENT, PROCEDURES AND TEST PARAMETERS	9
3.0	GUARDRAIL TEST	.11
4.0	TEST RESULTS	.20
5.0	SUMMARY OF FINDINGS	.21
6.0	Appendix: Load Cell Calibration Certificate	.22
7.0	Appendix: Guardrail dwg 08-01. Rev. IR. dated 10/21/08	.24
8.0	Appendix: dwg HEAMS106103 Rev. 0, dated 4/17/07	.28



List of Figures

Figure 1-1	STEELDECK® Guardrail Modules	1
Figure 1-2	Typical STEELDECK [®] Guardrail Mounting Joint	3
Figure 1-3	Typical STEELDECK® Guardrail Mounting Joint, view looking towards platform	4
Figure 1-4	Typical STEELDECK® Guardrail Mounting Joint, view from under platform	5
Figure 1-5	Manufacturer's "Company Test"	7
Figure 2-1	Test Setup	9
Figure 2-2	Test Setup, Outboard direction	10
Figure 2-3	Test Setup, Outboard direction	10
Figure 3-1	Elastic Deflection, Outboard Test #1 loaded to 207.1 lbs	11
Figure 3-2	Outboard Test #1 loaded to 207.1 lbs	12
Figure 3-3	Elastic Deflection, Inboard Test #2 loaded to 214.4 lbs	13
Figure 3-4	Inboard Test #2 loaded to 214.4 lbs	14
Figure 3-5	Elastic recovery after tests #1 & #2	15
Figure 3-6	Elastic Deflection, Outboard Test #3 loaded to 382.1 lbs	16
Figure 3-7	Outboard Test #3 loaded to 382.1 lbs	17
Figure 3-8	Elastic recovery after test #3	18
Figure 3-9	Guardrail bottom joint after tests #1-3	19



List of Tables

Table 2-1	Loading Sequence & Procedure	18
-----------	------------------------------	----

Rev. B



References

- 1. 2007 California Code of Regulations, Title 24, Part 2, California Building Code
- 2. 2001 California Code of Regulations, Title 24, Part 2, California Building Code
- 3. 1994 Uniform Building Code, Volume 2, Structural Engineering Design Provision.
- 4. Steeldeck, Set-up and Safety Manual, Rev. 5/2002.
- 5. Steeldeck, Platform Systems Catalog, May 2002.
- 6. British Standards Institution Specification BS 1139: Part 2: 1982, Metal Scaffolding.
- British Standards Institution Specification BS EN 74-1:2005, Couplers, spigot pins and baseplates for use in falsework and scaffolds, Part 1: Couplers for tubes – Requirements and test procedures.
- 8. 4'x 8' Steeldeck[®] Platform Evaluation, Rev. 1 dated April 2007, Hopper Engineering Associates, PRO 196
- 9. OE Document No.: OE-08-05-301, Test Report: Steeldeck Platform Systems Structural Capacity, Rev. B Dated March 11, 2014.
- 10. 2013 California Code of Regulations, Title 24, Part 2, California Building Code
- 11. 2016 California Code of Regulations, Title 24, Part 2, California Building Code



Rev. C Section 1.0

1.0 INTRODUCTION

This test report presents independent testing and findings conducted by Odian Engineering of the Guardrails used on the Steeldeck® platform system. The prior Revision "IR" of this report presented the testing conducted to substantiate the structural integrity of the subject Guardrail system by way of live load testing consistent with the current 2007 California Code of Regulations, Title 24, Part 2, Chapters 16 & 17. Subsequent Revision "A" of the test report showed continued compliance with the then current 2013 California Code of Regulations, Title 24, Part 2, Chapters 16 & 17. This subsequent Revision "C" of the test report shows continued compliance with the current 2016 California Code of Regulations, Title 24, Part 2, Chapters 16 & 17. A standard 4 ft. Guardrail assembled to a 4'x 4' deck in accordance with the manufacturer's Set-up and Safety Manual (Ref. 4) was tested herein. This configuration represents the typical modular installation which can be repeated side by side for longer rail configurations. The rail modules do not interconnect and they function independently of the neighboring modules, thus this unit test bounds all rail configurations.









1.1 Background

Steeldeck manufactures platform systems for sale and rent. These systems are typically employed as assembled platforms in various private and sometimes public venues. Often, the platforms are assembled as a connected system to erect a large platform of variable shape. This is accomplished by virtue of the modular design and the ability to connect the individual platforms of different sizes and shapes together. The platforms which contain straight edges can be fitted with modular Guardrails.

As previously stated, a system of one 4x 4 deck assembled with a single Guardrail was selected as the test configuration. This configuration was selected since it represents the typical modular installation, on which the critical loading per California Code of Regulations was to be applied.

The Guardrail system is comprised of the rail body, support pins (fixed to the leg bottom plates), two backing plates and two mounting bolts. When fitting a given platform with the Guardrail system, the rail is engaged to the platform by setting the support pins onto the lower chord of the platform truss. The backing plates are then positioned and clamped down with mounting bolts. The following figures show Guardrail installation. Note that the Guardrails are offered in three different widths: 2', 3' & 4'.







Typical STEELDECK® Guardrail Mounting Joint



Rev. A Section 1.0



Figure 1-3 Typical STEELDECK[®] Guardrail Mounting Joint, view looking towards platform



Rev. A Section 1.0



Figure 1-4 Typical STEELDECK[®] Guardrail Mounting Joint, view from under platform



1.2 Test Objective

The 2016 California Code of Regulations, Title 24, Part 2, Chapters 16, Table 1607.1, Minimum Uniformly Distributed Live Loads and Minimum Concentrated Live Loads, and Section 1607.8 establishes the required loading for Railings and Guardrails as 50 lbs per linear foot or 200 lbs applied in any direction at any point on the rail. Section 1709 of the same code sets forth In-Situ Load Test methodology. Consistent with the intent of Section 1709, the objective of this testing was to subject the Guardrail in excess of the required design load in the most critical directions and location. The test procedure employed has been developed by this author, a registered Professional Engineer in the State of California. The test procedure simulates loads and conditions of application that the Guardrail structure may be subjected to in normal use. The structure shall be considered to have successfully met the test requirements when the following criteria are satisfied:

- 1. The Guardrail shall be capable of withstanding the applied design load (200 lbs) without separating or otherwise catastrophic failure.
- 2. Upon removal of the test load, the structure shall have undergone no gross permanent deformation.

1.3 Previous Work

The subject Guardrail systems, as designed, have been in use for over 20 years primarily in the entertainment industry. They have been subjected to on the job in-situ loading reportedly without any catastrophic incident. The typical on the job loading demands placed on the Guardrails is far less than the aforementioned design requirements.

The manufacturer conducted a similar test as that proposed herein; "Company Test". He supported a 4' x 4' Steeldeck rental platform vertically, about six inches off the ground using various lengths of pipe and scaffolding fittings. He then attached a rental 4' guardrail to this 4' x 4' platform. He elected to use Schedule 40 1 $\frac{1}{2}$ " pipe as the test load, which weighs 2.72 pounds per linear foot. Using 4' steel pipes, which weigh 10.88 pounds each, 207.72 pounds (19 pipes) was applied to the top of the rail, acting vertically down. The guardrail deflected down about $\frac{1}{2}$ " from its unloaded resting position. When the load of pipe was removed, and the deck and guardrail disassembled, no damage was reported on any components. A photograph of this



"Company Test" is shown below. The "Company Test" loading was not necessarily localized at a single point, at the most critical location.



Figure 1-5 Manufacturer's "Company Test"



1.4 Limitations

The results of the testing proposed herein is limited to the following:

- 1. Guardrail modules made of the same grade and configuration as that which was tested (per Steeldeck dwg 08-01 Rev. IR, dated 10/21/08) and installed in accordance with Reference 4. Inclusive of the shorter 2' & 3' width versions which are less critical.
- 2. Guardrail modules affixed to platforms made of the same grade and truss beam configuration as that which was tested (per dwg HEAMS106103 Rev. 0, dated 4/17/07).



Rev. B Section 2.0

2.0 EQUIPMENT, PROCEDURES AND TEST PARAMETERS

One 4' x 4' rectangular platform was erected on a flat concrete floor inside a warehouse. One 4' modular section of Guardrail was affixed to the platform on one end, while the opposite end was fixed to rigid structure by way of tie down straps. The platform conformed to dwg HEAMS106103 Rev. 0, and was set on 3' legs (1-1/2 Schedule 40 steel pipe). All aforementioned platform systems components were adjoined together as per the standard procedures outlined in Reference 4. All equipment and hardware were randomly selected from rental stock to ensure a typical "as used" condition. Outboard, and then inboard, horizontal normal loads were imparted to an upper corner (critical single side loading and max bending lever arm) via cargo straps with ratcheting tensioners. In series with the load line was a Chatillon load cell, model DFE-500 (S/N T09409) in current calibration traceable to National Standards (see Appendix).



Figure 2-1

Test Setup



Rev. B Section 2.0



Figure 2-2 Test Set

Test Setup, Outboard direction



Figure 2-3 Test Setup, Outboard direction



3.0 GUARDRAIL TEST

On April 16, 2008, this author conducted the Guardrail tests as described in the preceding chapter. All phases of the test equipment erection, loading and unloading were witnessed by this author.

First, a live load consisting of 207.1 lbs (Design requirement = 200 lbs) was applied to the Guardrail corner in the outboard direction away from the platform.



Figure 3-1 Elastic Deflection, Outboard Test #1 loaded to 207.1 lbs



Rev. A Section 3.0



Figure 3-2 Outboard Test #1 loaded to 207.1 lbs



Then, a live load consisting of 214.4 lbs (Design requirement = 200 lbs) was applied to the Guardrail in the inboard direction towards the platform.







Rev. A Section 3.0



Figure 3-4 Inboard Test #2 loaded to 214.4 lbs



Rev. A Section 3.0



Figure 3-5 Elastic recovery after tests #1 & #2



Then, a live load consisting of 382.1 lbs (Design requirement = 200 lbs) was applied to the Guardrail in the outboard direction away from the platform. This third test was done for conservatism in excess of the Design Requirement by approximately 190%.



Figure 3-6 Elastic Deflection, Outboard Test #3 loaded to 382.1 lbs



Rev. A Section 3.0





Outboard Test #3 loaded to 382.1 lbs



Rev. A Section 3.0





Table 2-1 Loading Sequence & Procedure

Load Step	Applied Load (lbs)	Apprx. Dwell Time (min)
1	207.1	3
2	214.4	9
3	382.1	5

Odian Engineering Inc. 29979 Harvester Rd., Malibu, CA. 90265 Telephone (818) 371.7128 e-mail: kodian@verizon.net



Rev. B Section 3.0

Intermediate inspections and teardown inspections of the test articles were carried out by this author. No detrimental distress or failure was observed.



Figure 3-9Guardrail bottom joint after tests #1-3



4.0 TEST RESULTS

The structure successfully met the test requirements as follows:

1. The Guardrail shall be capable of withstanding the applied design load (200 lbs) without separation or otherwise catastrophic failure.

Result: At no time during the test or upon teardown inspection were any failures evident. The maximum 382.1 lbs critical outboard test was 191% of the Design Load requirement.

2. Upon removal of the test load, the structure shall have undergone no gross permanent deformation.

Result: The tested Guardrail system recovered elastically with no permanent set upon unloading.



5.0 SUMMARY OF FINDINGS

The subject Steeldeck[®] Guardrail fabricated in accordance with Steeldeck dwg 08-01, Rev. IR dated 10-21-08, and affixed to Steeldeck[®] platforms fabricated with the same grade and construction as per dwg HEAMS106103 Rev. 0, dated 4/17/07, were found to meet and exceed the minimum performance standards of applicable 2016 California Code of Regulations, Title 24, Part 2.

A Design load rating of 200 lbs is acceptable for these Steeldeck[®] Guardrails.



6.0 Appendix: Load Cell Calibration Certificate.





Rev. A Section 6.0

APPERS V.V. VSTR		AN AN ANA		
	AS DECE	IVED	AS CALIRRA	TED
TEST (LBF) STANDARD	TENSION	COMPRESSION	TENSION	COMPRESSION
100.0	0.0	0.0	-100.0	100.4
200.0	0.0	0.0	-200.0	200.4
300.0	0.0	0.0	-300.0	300.4
400.0	0.0	0.0	-399.9	400.4
500.0	0.0	0.0	-499.9	500.5
0.0	0.0	0.0	0.0	0.0
1 THE ABOVE I	ISTED RESULTS REL	ATE ONLY TO THE MO	DEL AND SERIAL	JUMBER OF
THE UNIT AS	SPECIFIED ON THIS	CERTIFICATE OF CALI	BRATION.	
2. CALIBRATIO	N PERFORMED AT 7	1.24 DEGREES F AND	5.60 % R.H.	
3. THIS CERTIFI	CATE OF CALIBRAT	ION SHALL NOT BE REI	PRODUCED EXCEP	TIN FULL,
WITHOUT TH	E WRITTEN APPROV	AL OF AMETEK, INC.		
4. CALIBRATIO	N STANDARDS HAVE	A ONE YEAR CALIBR	ATION CYCLE.	1 690
5. THE CONFIDE	INCE LEVEL ON UNC	LEKTAINTY STATEMEN	15 15 95% (K=2) UN	LESS
CTTLIC WISE	and the second s			
	CALIB	RATION TRACEABIL	ITY	
REFERENCE	WORK STATIC	ON CALIBRA	TION ID C	AL STD DUE DATE
WEIGHT SET	WS2	170-	069	7/28/2008
TY	PICAL MEASUREN	MENT UNCERTAINTY	= 0.033% OF FUL	L SCALE
AMETEK Tes	and Calibration Instr	uments Division certifies	that the product ref	erenced in the
Certificate meet	s specifications; and,	further certifies that the r	eferenced instrumen	t was serviced
and/or calibrate	d using quality and ma	anufacturing systems gov	erned by the require	ments of ISO 9001
registered comp	liant, file UL A4716.			
	Λ			
	1 0 1	1.		
	1 that	lle and a		
Collimated has	any fles	ADDROVED DV:		
Calibrated by:	ATHA MILINIA		CERTIFIED OPEN	ATOR
Calibrated by: MAI	RTHA MURILLO		CERTIFIED OPEN	RATOR
Calibrated by: MAI	10/12/2007	Date:	CERTIFIED OPEI 10/12/2007	RATOR
Calibrated by: MAJ	10/12/2007	Date:	CERTIFIED OPEI 10/12/2007	RATOR
Calibrated by: MAJ Date:	10/12/2007	Date:	CERTIFIED OPEI 10/12/2007	RATOR
Calibrated by: MAJ Date:	10/12/2007	Date:	CERTIFIED OPEI 10/12/2007	CATOR
Calibrated by: MAJ MAJ Date:	RTHA MURILLO 10/12/2007 Report Nu	Date:	CERTIFIED OPEI 10/12/2007 PAG	E 2 OF 2
Calibrated by: MAJ MAJ Date:	RTHA MURILLO 10/12/2007 Report Nu	Date:	CERTIFIED OPEI 10/12/2007 PAG	E 2 OF 2
Calibrated by: MAI MAI	RTHA MURILLO 10/12/2007 Report Nu	Date:	CERTIFIED OPEI 10/12/2007 PAG	E 2 OF 2
Calibrated by: MAJ MAJ Date:	RTHA MURILLO 10/12/2007 Report Nu	Date:	CERTIFIED OPEI 10/12/2007 PAG	E 2 OF 2

23



Rev. B Section 7.0

7.0 Appendix: Guardrail dwg 08-01, Rev. IR, dated 10/21/08



Rev. B Section 7.0



29979 Harvester Rd., Malibu, CA. 90265

Telephone (818) 371.7128 e-mail: kodian@verizon.net



Rev. B Section 7.0



Odian Engineering Inc. 29979 Harvester Rd., Malibu, CA. 90265 Telephone (818) 371.7128 e-mail: kodian@verizon.net



Rev. B Section 7.0



Odian Engineering Inc. 29979 Harvester Rd., Malibu, CA. 90265 Telephone (818) 371.7128 e-mail: kodian@verizon.net



Rev. B Section 8.0

8.0 Appendix: dwg HEAMS106103 Rev. 0, dated 4/17/07



Rev. B Section 8.0



Odian Engineering Inc. 29979 Harvester Rd., Malibu, CA. 90265 Telephone (818) 371.7128 e-mail: kodian@verizon.net



Rev. B Section 8.0



Odian Engineering Inc. 29979 Harvester Rd., Malibu, CA. 90265 Telephone (818) 371.7128 e-mail: kodian@verizon.net